

Tunneling Towards Sustainability: Comparative Analysis of Urban Water Management in Washington D.C. and London

Xinjia Huang *

Bartlett School of Sustainable Construction, University College London, London, WC1E 6BT,
United Kingdom

* Corresponding author: xinjia.huang.23@ucl.ac.uk

Abstract. This paper examines the crucial role of underground tunnels in urban water management, specifically focusing on two projects: the Anacostia River Tunnel in Washington D.C. and the Thames Tideway Tunnel in London. This analysis emphasizes the challenges and opportunities associated with such infrastructure development in addressing urban water pollution and strengthening sewage treatment systems. Through a comprehensive review of these projects, this paper discusses their environmental and social impacts, cost effectiveness, as well as lessons learned during construction and operation phases. Additionally, it addresses the broader theoretical framework of integrated water resources management, illustrating how tunnel projects can significantly enhance urban flood management, water quality, and social welfare. Drawing upon various studies, it explores the integration of green and grey infrastructure in urban environments while emphasizing the need for comprehensive and sustainable solutions for managing urban water resources. Overall, this paper contributes to understanding the critical role of tunnel engineering in contemporary urban environments while providing insights for research and development within public infrastructure for environmental management.

Keywords: Tunnel project, sustainability, urban water management.

1. Introduction

Tunnel projects play a pivotal role as part of innovative infrastructure solutions in managing urban runoff and sewage treatment. By constructing underground tunnels, flooding can be effectively prevented by capturing excessive rainwater during heavy rainfall events and diverting it away from cities. Moreover, these tunnels can enhance water quality by intercepting polluted runoff before it reaches water bodies, thus reducing the influx of pollutants into rivers and oceans. The implementation of an underground tunnel system introduces a more reliable and resilient infrastructure to the urban water transportation and storage network while further advancing its goals in wastewater treatment.

Based on the significant contribution of underground tunnels to water and sewage treatment, countries worldwide have sequentially implemented tunnel projects near major cities and river basins. In Washington, D.C., the Anacostia River Tunnel project commenced construction in 2013 as a crucial component of the Clean River initiative and was officially completed in 2018. Serving as a substantial investment in the nation's capital infrastructure, this tunnel project aims to substantially mitigate confluence sewer overflows (CSO) into the Anacostia River, thereby enhancing basin water quality, public health, and contributing to ecological restoration efforts. Similarly, Thames Tideway Tunnel, which commonly referred to as the 'super sewer', has been undertaking construction since 2016 in London, with an anticipated completion date of 2025. Aligning with its counterpart in Washington D.C., the Thames Tideway Tunnel seeks to intercept, store, and divert raw sewage that currently overwhelms the Thames while addressing pollution issues stemming from London's aging Victorian sewer system. Consequently, it will support river biodiversity restoration endeavors and improve overall well-being for residents of London.

This paper will take the Anacostia River Tunnel project, which has been successfully completed and put into operation, as the main research object. The study also identifies lessons learned from the construction and operation process of the project. Additionally, drawing upon insights gained from the Anacostia River tunnel project analysis and experience summary, this paper will propose

recommendations for enhancing and optimizing the Thames Tideway Tunnel Project in conjunction with the specific circumstances of this London tunnel project, aiming to explore potential areas for further research and development.

2. Literature Review

Tunnel engineering plays a crucial role in urban water management by enhancing water supply, improving flood drainage, and maximizing economic and social welfare impact. This is exemplified in the research of the Apos elemis Dam and Tunnel public water project in northeastern Crete, Greece [1]. For instance, it involves diverting uphill surface water from the Lasith Plateau into reservoirs while also discharging excess water, which contributes significantly to improving the quality of urban water supply and effectively managing floods. Additionally, it also supports agricultural activities on the plateau and reduces the vulnerability of cities to flood-related damage [1]. Other studies discussing grey infrastructure's capacity for urban flood prevention highlights that deep tunnels can substantially reduce peak flood volume and duration. This suggests their pivotal role in efficiently managing large volumes of stormwater as well as surface runoff [2].

The Greek dam and tunnel project conducted an environmental impact assessment (EIA) that emphasized the need for ongoing environmental monitoring and implementation of sustainable agricultural practices to mitigate negative impacts on water quality. This study also demonstrated the technical feasibility and effectiveness of combining tunnel technology with dam construction, providing examples of how large-scale infrastructure projects can support sustainable development goals [1]. However, it is important to note that the advantages of tunnel engineering in urban water management are not exhaustive. Some researchers have indicated that while tunnel projects as grey infrastructure possess significant stormwater management capabilities, they exhibit limited effectiveness in mitigating local flooding caused by inadequate sewer capacity and may potentially transfer the problem downstream [2]. Therefore, this research advocates for the establishment of a theoretical framework that integrates both grey and green infrastructure, offering a more comprehensive solution for urban management by harnessing the capacity management capabilities of tunnel light grey infrastructure alongside the absorption and filtration benefits provided by green infrastructure [2].

It is also crucial to also focus on the environmental and economic benefits as well as the challenges it faces, particularly regarding pollution treatment and control, cost efficiency, and sustainable urban development. A study conducted by Dolowitz, Bell, and Keeley examined the retrofitting of urban drainage infrastructure with a specific emphasis on the Thames Tidal Tunnel in London [3]. This study provided valuable insights into both the environmental and economic advantages as well as challenges associated with tunnel projects. In terms of environmental benefits, tunnel projects can capture and redirect sewer overflows to mitigate pollution levels and enhance water quality, thereby improving aquatic ecosystems [3]. From an economic perspective, reduced water pollution and flood damage along with decreased maintenance costs for urban drainage systems can result in significant long-term savings. Additionally, constructing tunnel projects represents a substantial investment in critical infrastructure that can stimulate economic activity while creating job opportunities [3]. However, it is important not to overlook that tunnel engineering is a resource-intensive infrastructure endeavor which may increase carbon emissions during construction and operation phases, thus posing a challenge to achieving sustainable urban development goals. Furthermore, concerns about feasibility arise due to cost overruns and delays caused by complexities or unforeseen technical issues commonly encountered in large-scale infrastructure projects. The financial difficulties faced by the Thames Tideway Tunnel serve as evidence supporting this viewpoint [3].

It is worth noting that most studies in the literature concentrate on short-term environmental and social impacts of tunnel engineering while neglecting its long-term effects on water quality and biodiversity. Obviously, there is a lack of comprehensive comparative analysis among tunnel projects under different geographical and socio-economic backgrounds in existing literature. The varying

levels of economic development and social needs may significantly influence the implementation as well as effectiveness of tunnel engineering initiatives. Lastly, an important aspect that has been overlooked in the literature is the significance of community participation throughout the project planning process. Such involvement not only enhances social acceptance but also contributes to long-term sustainability and efficiency improvements.

This paper focuses on the Anacostia River Tunnel project in Washington, D.C., as a primary case study to conduct a comprehensive analysis of its costs and environmental benefits. Furthermore, it will be compared with the Thames Tideway Tunnel in London to explore the sustainability and socio-economic impact of tunnel projects within similar contexts but different environments. Additionally, the study aims to provide novel insights and optimization recommendations for water management in the Thames River through a comparative analysis of these two tunnel projects, thereby advancing knowledge and practical applications in this field.

3. Research Design

3.1. Project Background

More than a century ago, approximately one-third of the District of Columbia relied on combined sewer systems that merged sewage and stormwater. Only in recent years, Washington, D.C. has commenced the installation of a separate sewerage system with distinct pipelines. However, due to pipeline aging and population growth, heavy rainfall leads to significant combined sewer overflow (CSO) occurrences within the old city. Consequently, nearby residents and water bodies suffer from heightened pollution caused by bacteria and waste materials. To comply with the U.S. Environmental Protection Agency's regulations for reducing CSOs into adjacent water bodies, the District of Columbia Water and Sewerage Authority (DC Water) is actively implementing its Long-Term Control Plan (LTCP) to ensure effective protection of the water environment both presently and in the future, and the Anacostia River tunnel plays a crucial role in this comprehensive solution [4].

Serves as a crucial final component of the initial phase of the DC Clean River Project, the Anacostia River Tunnel in Washington, D.C. is primary to alleviate consolidated sewer overflows that currently discharge into the Anacostia River by collecting and conveying them to the Blue Plains Advanced Wastewater Treatment Plant for proper treatment, after which they are discharged into the Potomac River. This reinforced concrete tunnel has a diameter of 23 feet and spans approximately 2.37 miles from northeast to southeast Washington, D.C. In addition to the underground tunnel section, DC Water has constructed various surface facilities along its route including deep wells and large concrete structures to effectively divert sewer overflows towards the tunnel. With its completion and commissioning in March 2018, the Anacostia River Tunnel significantly increased project's combined sewage capacity to 100 million gallons while reducing combined sewer overflows into the Anacostia River by nearly 90%. This achievement marks a significant milestone for DC Water's commitment towards fulfilling requirements outlined in Clean River Project consent decree and represents a perfect conclusion to this first project phase with anticipated positive outcomes.

3.2. Cost Analysis

As an environmental initiative aimed at mitigating adverse impacts on the river and promoting sustainability, the Anacostia River Tunnel project has significant implications for ecosystems, biodiversity, and community health and well-being. Simultaneously, it is also an infrastructure project that entails substantial capital investment and resource allocation. Therefore, conducting a comprehensive cost analysis becomes imperative to ensure efficient resource utilization by project owners and attainment of long-term environmental and social objectives. This paper focuses on scrutinizing DC Water's financial disclosures pertaining to the actual expenditures incurred in implementing the Anacostia River Tunnel project as well as examining its funding sources and strategies employed for effective cost management.

One of the largest construction projects ever undertaken in Washington D.C is the Clean Rivers Project by DC Water. With a total cost of approximately \$2.7 billion, its objective is to eliminate confluence sewer overflows on the Anacostia River, Potomac River, and Rock Creek while improving the health of the Chesapeake Bay. The first phase of this project, known as the Anacostia River Tunnel, was completed on time in 2018 after five years of construction at a total cost of approximately \$254 million. Furthermore, through implementing low-impact development practices for water and wastewater treatment facilities across the region (LID-R) and providing technical and regulatory assistance to local governments, it successfully reduced actual costs by approximately 1.7%, equivalent to \$13 million less than budgeted expenditure. In fact, DC Water has been strategically planning and meticulously preparing for the governance of combined sewer overflows (CSOs) in the Anacostia River Basin for over a decade. As early as 2002, DC Water devised a comprehensive long-term control plan for the combined sewage system, which clearly delineated alternative routes for the Anacostia River tunnel. The existing Anacostia River tunnel obviates the necessity of constructing a new pumping station and pipeline to Poplar Point, resulting in substantial cost savings estimated at \$300 million to \$375 million compared to Alternative One's proposed tunnel from Poplar Point to the Northeast Boundary. Consequently, this infrastructure project witnesses significant reductions both in terms of scale and expenditure. Enhanced engineering content coupled with diminished construction costs rendered other alternatives ineligible for consideration while solidifying selection of the current route for implementation of the Anacostia River Tunnel.

Furthermore, from the initial stage of construction to project completion, approximately \$210.8 million of the Anacostia River Tunnel project's actual cost was funded by federal sources, while local taxpayers covered the remaining expenses. In 2015, DC Water also became the first water and wastewater company in the United States to issue century bonds with a final maturity period of 100 years. This innovative approach not only aligns better with the tunnel's expected lifespan but also strategically spreads construction costs across generations of benefiting taxpayers. Additionally, during the construction process, DC Water collaborated with three specialized companies to collectively undertake and execute various aspects of the tunnel project. By meticulously dividing and bidding out different components of this project scope, DC Water effectively maximizes cost benefits while minimizing external factors' impact on overall expenses and alleviating financial pressures.

3.3. Benefit Analysis

The Anacostia River Tunnel project has yielded numerous advantages in terms of enhancing water quality, restoring biodiversity and improving urban livability. Given its environmental focus during planning and construction, this paper aims to primarily analyze the intangible benefits generated by the project and specifically examine its impact on both the environment and society when defining the scope of benefit analysis. Through a meticulous assessment of these intangible benefits associated with the Anacostia River Tunnel, this paper also seeks to present a comprehensive overview of how it contributes to community welfare and environmental integrity. Furthermore, it endeavors to enable stakeholders to recognize the extensive range of benefits offered by such tunnel projects while providing broader support for informed decision-making on similar ventures in future.

3.3.1. Environmental benefits

Prior to its opening, an average of 2.1 billion gallons of untreated sewage was discharged directly into the waterways in Washington D.C., each year, with the region's aging sewers overflowing into the Anacostia River 84 times annually [5]. However, with the completion and operation of the tunnel's first phase, approximately 15 billion gallons of untreated sewage and stormwater as well as nearly 9,800 tons of domestic and industrial waste have been prevented from entering the Anacostia River [5]. Consequently, there has been a significant improvement in water quality within the watershed.

Moreover, through long-term water quality testing and assessment conducted by the District of Columbia Department of Energy and Environment (DOEE), it was found that by four years after commissioning the tunnel project, the water transparency in the Anacostia River watershed had

significantly increased on average by more than 50% in 2022 [6]. Prior to completing construction on the tunnel project, algal blooms were prevalent in the watershed due to confluence discharge from urban areas and nutrient runoff from surrounding landscapes. This resulted in frequent low-oxygen dead zones within the Anacostia River. However, since implementing this tunnel project for use according to DOEE monitoring data shows a decrease in chlorophyll-A levels within recent years. Although the reduction rate is less than 50%, it still indicates a tendency towards balanced algae growth within this watershed [6]. This serves as another indication that both health and water quality conditions are recovering for The Anacostia River.

In addition to enhancing water quality, the Anacostia River tunnel has made a significant contribution to reducing river pollution. Firstly, since its completion and commissioning in March 2018, this tunnel alone has reduced CSO emissions into the Anacostia River by 81% [7]. Even more exciting is that DC Water's final planned downstream Northeast Boundary tunnel in Phase 1 will assist the Anacostia River Tunnel in achieving up to 98% of CSO reductions in the Washington region, surpassing Philadelphia's 60% and New York's 40%, which marks the DC Water Clean Rivers Project truly aims to make the Anacostia River watershed the cleanest body of water in the region. Additionally, while aiming to reduce CSOs within the river watershed, this project also targets nitrogen reduction flowing into Chesapeake Bay by up to one million pounds per year, thus significantly mitigating eutrophication and other pollution hazards [7, 8].

Even more astonishingly, the 2020 State of the River report by the Anacostia Watershed Association reveals that, owing to the commendable performance of the Anacostia River tunnel, the submerged aquatic vegetation (SAV) in the river has made a complete recovery for the first time. Prior to the construction of the tunnel in 2018, aquatic plants in the river were well below the threshold of 20 acres. However, by 2020, there was a rapid expansion in aquatic plant coverage to an impressive 92.6 acres with a remarkable reference score of 100% [9]. This phenomenon vividly demonstrates rivers' robust self-cleaning and ecological restoration capabilities after reducing pollution and improving water quality. Furthermore, freshwater mussels have become one of North America's most endangered animal groups due to water pollution and habitat destruction, within already 37 species considered extinct. Since 2019, over 24,000 mussels have been released into the Anacostia River by The Anacostia Watershed Association as its water quality gradually returns to standards suitable for breeding these freshwater mollusks. This initiative not only enables mussels to assist plants by serving as substrates for algae and aquatic flora but also provides habitats for other benthic invertebrate species through their shells. Most importantly, as filter feeders, mussels effectively remove suspended sediment from water bodies thereby enhancing water transparency, which further contributes towards improving overall water quality within The Anacostia River and augmenting its entire aquatic ecosystem.

3.3.2. Social benefits

Since the 1980s, the Anacostia River has faced a critical condition due to severe pollution issues such as stormwater runoff and inadequate sewage treatment. In recent years, significant progress has been made towards restoring the river's health through initiatives like the DC Water Clean River Project and the successful completion of the Anacostia River Tunnel. However, it is important to recognize that these efforts mark just the initial steps in addressing long-term governance and biodiversity challenges within the watershed. Despite their willingness to contribute, ordinary individuals often lack sufficient understanding of these complex problems, limiting their ability to effect meaningful change.

Thus, within the framework of a new wave of river conservation inspired by the successful implementation of the tunnel project, since 2018, the Anacostia Watershed Association has been dedicated to actively involving residents of all age groups in meaningful educational programs aimed at comprehending the challenges faced by the river and raising awareness regarding watershed preservation. This is achieved through offering practical and theoretical courses tailored for different age brackets, equipping participants with essential skills and management knowledge to contribute towards ongoing community efforts focused on safeguarding and restoring the ecological balance.

Simultaneously, in collaboration with DC Water, the District of Columbia Department of Energy and Environment (DOEE) has undertaken various initiatives to educate and motivate communities as well as residents residing within this watershed about the crucial link between waste convergence and river health. For instance, under its program funding scheme for innovative water quality improvement projects within local communities, DOEE aims to encourage these communities along with their inhabitants to proactively reduce pollution at its source before it enters water bodies. In conjunction with these endeavors aligned with the tunnel project's objectives, effective measures will be implemented to ensure that cleanliness is maintained throughout the Anacostia River watershed.

In fact, the construction of the Anacostia River tunnel has significantly accelerated the development of community and commercialization along the river. In 2015, a \$10 million grant from the U.S. Department of Transportation was awarded to complete the 20-mile Anacostia Riverwalk that spans both sides of the river [10]. Serving as a vital artery for residents, visitors, communities, and businesses alike, this Riverwalk aims to establish a new public facility and recreational space for the local waterfront community while highlighting the pristine condition of the river. Furthermore, ethnic communities have increasingly embraced and celebrated their connection with the Anacostia River environment and culture due to its positive impact resulting from tunnel construction. The inaugural "Anacostia River Festival" in 2016 was extravagantly celebrated with activities such as boat tours, traditional cuisine offerings, and games specifically designed to foster a stronger bond between Latino community members and their involvement in ecological restoration efforts related to the Anacostia River [10].

More significantly, the entire process of the Anacostia River tunnel project, from its inception to completion, has profoundly stimulated the local economic market and employment environment. In 2012, when construction of the tunnel project commenced, DC Water entered into a partnership agreement with the District of Columbia and the U.S. Environmental Protection Agency (EPA) to advance green infrastructure in the region. The objective is also to achieve sustainable stormwater management and foster more livable riverside communities while simultaneously generating positive economic performance by enhancing property values and supporting green jobs. Moreover, DC Water offers training opportunities for residents interested in pursuing careers related to green infrastructure construction and maintenance with an aim to have community residents fill 51% of new job positions created by the Anacostia River Tunnel project.

4. Result Discussion

The research demonstrates the substantial impact of the Anacostia River Tunnel project on environmental enhancements, particularly in terms of water quality improvement and biodiversity preservation within the river watershed. Since its completion, this project has effectively mitigated confluence sewer overflows and successfully intercepted sewage and waste, resulting in a qualitative amelioration of the Anacostia River's water quality within just four years. It is not solely about restoring cleanliness to the river, rather improved water quality directly contributes to the revitalization and rehabilitation of aquatic ecosystems as well as flora and fauna habitats. The accelerated proliferation of aquatic plants and reintroduction of filter-feeding shellfish are direct consequences of reduced pollutant loads and enhanced water conditions, thereby underscoring how this tunnel project aids in augmenting the river's self-purification capacity.

In addition, the Anacostia River Tunnel project has had a significant impact on the social landscape of the surrounding riverside communities, signifying substantial progress in community engagement and revitalization efforts. Following the completion of the tunnel, the Anacostia Watershed Association has initiated numerous hands-on projects aimed at educating residents about the challenges confronting the river and emphasizing watershed protection, while also fostering increased participation in river cleanup activities. Simultaneously, with the finalization of the Anacostia Riverwalk, not only does it provide space for community recreation and interaction but it also serves as a tangible representation of both ecological restoration and economic recovery within this

waterway. As environmental conditions along the Anacostia River continue to improve progressively due to these initiatives, job opportunities and real estate values generated by this tunnel project are attracting new businesses to this area, thereby contributing to broader discussions regarding sustainability and green jobs within this region that align with wider sustainable economic trends.

However, it is worth noting that the Anacostia River tunnel project has certain limitations. Specifically, when it comes to environmental and ecological restoration, relying solely on immediate data before and after tunnel construction may not fully capture long-term trends and delayed ecological responses. For instance, tests conducted in 2020 revealed that chlorophyll-A levels had decreased by less than 50 percent, indicating that nutrient levels in the water might still be higher than optimal for preventing future algal blooms. The limited duration of continuous monitoring from 2018 to 2020 makes it challenging to determine whether this is due to insufficient time for capturing long-term changes or because the tunnel alone cannot fully mitigate these issues, thus necessitating additional measures to address nutrient runoff. Similarly, while the reintroduction of mussels into the river because of water quality restoration signifies a positive step towards restoring the ecological complexity of the Anacostia River, there are no clear quantitative values or conclusions in the research that can definitively ascertain its effectiveness in promoting sustainable biodiversity growth. Therefore, observing and evaluating its impact on mussel survival and growth over an extended period becomes imperative.

Another drawback of the Anacostia tunnel project is its limited ability to eliminate the historical pollution deposited at the river's bottom, as it solely focuses on reducing existing stormwater and sewage overflows. The Anacostia River watershed has long been impacted by industrial activities, including naval shipyards, resulting in contaminated sediments in the water, shoals, and nearby land. Unfortunately, removing the remaining toxic sediment was beyond the scope of the tunnel project. As a result, DOEE collaborated with local landowners to develop an action plan for cleaning up river sediments as a follow-up to DC Water's Clean River program. This comprehensive plan requires an investment of \$35 million and aims to remove harmful pollutants by 2024 [11]. Despite significant progress made through initiatives like the Clean River Program and tunnel projects in controlling threats such as sewage and industrial toxins that affect water quality, recent intensification of extreme climate change has led to historic losses of wetlands and forests within the Anacostia watershed. Consequently, this exacerbates excessive runoff and pollution risks while potentially reversing three decades' worth of achievements in Washington region. Therefore, evaluating how effectively the Anacostia River tunnel can handle heavy rainfall events and flooding during extreme weather conditions becomes crucial for further testing and investigation.

Given the lessons learned from the aging of confluence sewers in the Washington, D.C., it is crucial to engage in discussions and develop a comprehensive maintenance framework that ensures continuous performance and addresses potential aging issues for this type of infrastructure, which requires significant investment in environmental health. Meanwhile, the financing strategy for the Anacostia River tunnel project heavily relies on federal funds, supplemented by issuing century bonds. While this financing approach is feasible, it somewhat shifts the funding burden of the project onto government entities and taxpayers. Therefore, future projects should explore innovative financing models such as corporate partnerships while actively observing best practices in cost management to enhance financial responsibility and efficiency.

5. Comparision of Anacostia River Tunnel and Thames Tideway Tunnel

5.1. Background and Comparative Analysis

As one of the key infrastructure projects in Washington D.C., the completion and operation of the Anacostia River tunnel project have significantly mitigated the issue of CSO in the area, making a lasting contribution to water quality restoration and ecological reconstruction efforts in the Anacostia River watershed. Shortly after its initiation, London embarked on a similar endeavor with planning approval granted for a super sewer beneath the Thames in 2014. Like its counterpart in Washington,

London's sewage system dates to Victorian times and has struggled to accommodate its rapidly growing population of 9 million people, resulting in millions of tons of untreated sewage being discharged into the Thames annually. To address this challenge and restore the health of their iconic river, Tideway Company collaborated with delivery partners such as Thames Water to construct the Thames Tideway Tunnel. This paper aims to compare these two tunnel projects based on project scale, financing mechanisms, and community engagement while offering valuable insights and recommendations for both ongoing construction activities and future operations related to London's ambitious undertaking.

The Anacostia River Tunnel and the Thames Tideway Tunnel share similar geographical characteristics. Both rivers, namely the Anacostia River in Washington and the Thames River in London, flow through major urban areas and encounter environmental challenges caused by excessive pollution from urban run-off and combined sewer overflows. Consequently, despite being situated in different countries, these tunnels offer valuable opportunities for comparison and mutual learning due to their comparable geography and shared obstacles.

Aligned with the primary objective of significantly reducing confluence sewer overflows in the Anacostia River Tunnel, the Thames Tideway Tunnel also aims to capture untreated sewage and is projected to achieve a 95% reduction in confluence sewer overflows within London's aging sewer system during a typical year. Furthermore, it is anticipated that the Thames Tidal Tunnel will contribute to mitigating sewage spills, including surface water run-off following heavy storms, from an annual average of over 50 incidents to approximately 5 incidents per year. Simultaneously, this tunnel will diminish the quantity of sewage-related waste entering the Thames while enhancing its water quality and providing habitat for diverse aquatic wildlife species to restore its rich and varied ecology.

In comparison to the 2.37-mile (3.8 kilometers) long Anacostia River Tunnel, the Thames Tideway Tunnel exhibits a significantly higher level of complexity in terms of scale and engineering capacity. Spanning across 25 kilometers from Acton in west London to Abbey Mills Pumping Station in east London, the Thames Tideway Tunnel boasts a diameter of 7.2 meters, while its depth ranges from an initial point at 31 meters and gradually slopes down to 66 meters. Additionally, it is estimated that four colossal tunnel excavators will be employed for the excavation of the main tunnel along with the construction of twenty-one shafts. Furthermore, its total storage capacity will amount to approximately 1.6 million cubic meters, equivalent to about 600 Olympic-sized swimming pools, which surpasses that of the Anacostia River Tunnel's sewage storage capabilities.

Moreover, there are also differences between the budget and funding of the two tunnel projects. Based on the cost analysis, the Anacostia River Tunnel has a total cost of only \$254 million, while the parent project, DC Water's Clean River program, has a total cost of approximately \$2.7 billion. However, with an estimated total investment of £4.2 billion, the Thames Tideway tunnel surpasses all tunnel projects combined under DC Water's Clean Rivers scheme in terms of costs. Moreover, the financing model for the Anacostia River Tunnel primarily relies on federal funds and century bonds, whereas for the Thames Tideway Tunnel it is relatively complex and diversified. For instance, out of the £4.2 billion total investment in the Thames Tidal Tunnel project, £1.1 billion is directly financed by Thames Water while £3.1 billion is financed by Tideway Company including shareholder funds amounting to £1.3 billion and loans from European Investment Bank totaling £700 million.

In terms of community engagement and stakeholder impact, the Anacostia River Tunnel project features an extensive program for community engagement and education aimed at raising awareness and gaining public support for a clean river. Conversely, the Thames Tideway Tunnel also involves significant stakeholder engagement efforts. However, due to geographical differences and varying levels of public awareness, its social engagement strategies' effectiveness may differ. From 2016 to 2024, Tideway employed over 1273 unemployed individuals throughout the entire project period, creating a social value exceeding £4.8 million in increased employment. Additionally, Tideway is encouraging young people to pursue STEM careers by partnering with more than 400 organizations that employ over 80,000 young people on the Thames Tideway Tunnel construction team. This

initiative not only injected dynamic new blood into the project's construction but also created more than £8 million in societal value.

5.2. Suggestions

Given the remarkable success achieved by the Anacostia River Tunnel in significantly reducing pollution overflows, it is strongly advised for the Thames Tideway Tunnel to adopt similar integrated pollution control measures. These measures should include implementing an advanced sewage filtration system as well as emergency overflow treatment facilities with utmost urgency to restore and maintain cleanliness levels within the Thames.

The Thames Tideway Tunnel enhance local support and awareness through regular updates, involvement in decision-making processes, and educational programs on pollution control. It is worth noting that both tunnel projects have played a crucial role in job creation and local economic development. In the case of the Thames Tideway Tunnel, particular emphasis can be placed on initiatives such as green jobs and related sustainable development while promoting local employment opportunities and fostering current economic growth.

As a costly public infrastructure, ensuring its effective maintenance planning and long-term sustainability is the most important issue. In this regard, the Anacostia River Tunnel itself does not serve as an exemplary model, as its related studies lack detailed information on future maintenance and addressing aging issues. Therefore, for both tunnel projects, proactive exploration of innovative financing options such as green bonds and sustainability-related loans should be undertaken in conjunction with the development of a comprehensive technical maintenance framework to ensure the long-term stability of the tunnel. This paper also strongly urges the Thames Tideway Tunnel project team to actively consider and incorporate the pertinent comments and suggestions provided herein, aiming to optimize both short-term outcomes and long-term impacts of the project.

6. Conclusion

The completion of the Anacostia River Tunnel has effectively mitigated the issue of combined sewage overflow (CSO) and significantly enhanced water quality, thereby facilitating the ecological restoration of the Anacostia River. The success of this project is evident in the substantial reduction in pollutants and restoration of local biodiversity, marking a pivotal shift towards achieving sustainable development goals for the city. Moreover, beyond environmental restoration, the tunnel's impact extends to active educational initiatives and job creation, fostering community engagement and promoting economic revitalization at a local level. The Thames Tideway Tunnel project aspires to replicate this success by addressing a similar challenge on London Thames River. This endeavor represents not merely an upgrade to aging infrastructure but also a crucial step towards environmental stewardship with its aim to substantially decrease sewage discharge into the Thames, safeguarding river ecology integrity while enhancing the life quality of London citizens.

Both projects demonstrate the crucial role of integrated infrastructure solutions in addressing urban environmental challenges. They highlight the necessity for innovative engineering approaches that encompass not only immediate technical requirements but also broader environmental, social, and economic impacts. The lessons learned from the Anacostia River Tunnel project offer valuable insights into the complexities of large-scale infrastructure projects, including strategic planning, community engagement, and adaptive management practices that can inform and enhance the execution of future tunnel projects such as Thames Tideway Tunnel.

In conclusion, the Anacostia River Tunnel and Thames Tideway Tunnel projects exemplify the potential of integrated water management solutions to revolutionize urban landscapes into more sustainable and habitable environments. The knowledge acquired from these projects will also be invaluable in guiding urban planning and achieving sustainable infrastructure development as cities continue to expand under emerging environmental challenges.

References

- [1] Vogiatzi C, Loupasakis C. Environmental impact of Aposelemis dam and tunnel water supply project in NE Crete, Greece. *Bulletin of the Geological Society of Greece*. 2021, 57 (1): 127 - 158.
- [2] Chen W, Wang W, Huang G, et al. The capacity of grey infrastructure in urban flood management: A comprehensive analysis of grey infrastructure and the green-grey approach. *International Journal of Disaster Risk Reduction*, 2021, 54: 102045.
- [3] Dolowitz DP, Bell S, Keeley M. Retrofitting urban drainage infrastructure: green or grey? *Urban Water Journal*, 2017, 15 (1): 83 - 91.
- [4] Beesley J, Colzani G, Allen C. Construction progress on the DC clean rivers project, *Industrial Report*, 2013.
- [5] Fenston J. New Anacostia River tunnel goes online will cut sewage overflows by 98%, *Research Report from DCIST*, 2023.
- [6] Gunnerson A. New data confirms that the Anacostia River is getting cleaner. *Research Report from Chesapeake Bay*, 2023.
- [7] Matuszeski B. Anacostia Tunnels help clean up river. *Industrial Report from Hill Rag*, 2024.
- [8] Pipkin W. New sewage-storing tunnel to transform polluted Anacostia River. *Research Report from Chesapeake Bay*, 2018.
- [9] Anacostia Watershed Society. River rebounds, earns highest passing grade so far. *State of the Anacostia River Report Card*, 2020.
- [10] United State Environmental Protection Agency. Program updates of Anacostia. *Research Report form EPA*, 2021.
- [11] Grablick C. The Anacostia River is getting a glow-up. *Research Report from NPR*, 2020.